

CERTIFICATE NO: _____

DATE ISSUED: _____

Application to the HISTORIC DISTRICT COMMISSION, Nantucket, Massachusetts, for a

CERTIFICATE OF APPROPRIATENESS

BFC - Garage
6 Sleetwing Cir

for structural work.

All blanks must be filled in using BLUE OR BLACK INK (no pencil) or marked N/A.

NOTE: It is strongly recommended that the applicant be familiar with the HDC guidelines, *Building with Nantucket in Mind*, prior to submittal of application. Please see other side for submittal requirements. Incomplete applications will not be reviewed by the HDC.

This is a contractual agreement and must be filled out in ink. An application is hereby made for issuance of a Certificate of Appropriateness under Chapter 395 of the Acts and Resolves of Mass., 1970, for proposed work as described herein and on plans, drawings and photographs accompanying this application and made a part hereof by reference.

The certificate is valid for three years from date of issuance. No structure may differ from the approved application. Violation may impede issuance of Certificate of Occupancy.

PROPERTY DESCRIPTION

TAX MAP N^o: 74 PARCEL N^o: 24
Street & Number of Proposed Work: 6 SLEETWING CIR
Owner of record: CANNONBURY HOLDINGS 2, LLC
Mailing Address: 105 NEWBURY STREET
BOSTON MA 02116
Contact Phone #: _____ E-mail: _____

AGENT INFORMATION (if applicable)

Name: ANDREW KOTCHEN (WORKSHOP/APD)
Mailing Address: PO BOX 521
NANTUCKET, MA 02554
Contact Phone #: 212-273-9712 E-mail: _____

FOR OFFICE USE ONLY

Date application received: _____ Fee Paid: \$ _____
Must be acted on by: _____
Extended to: _____
Approved: _____ Disapproved: _____
Chairman: _____
Member: _____
Member: _____
Member: _____
Member: _____
Notes - Comments - Restrictions - Conditions

DESCRIPTION OF WORK TO BE PERFORMED

See reverse for required documentation.

New Dwelling Addition Garage Driveway/Apron Commercial Historical Renovation Deck/Patio Steps Shed
 Color Change Fence Gate Landscaping Move Building Demolition Revisions to previous Cert. No. _____
 Pool (Zoning District _____) Roof Other _____

Size of Structure or Addition: Length: 25'-0" Sq. Footage 1st floor: 404 Decks/Patio: Size: _____ 1st floor 2nd floor
Width: 17'-0" Sq. footage 2nd floor: _____ Size: _____ 1st floor 2nd floor
Sq. footage 3rd floor: _____

Difference between existing grade and proposed finish grade: North 0' South 0' East 0' West 0'
Height of ridge above final finish grade: North 15'-4" South 15'-4" East 15'-4" West 15'-4"

Additional Remarks

Historic Name: _____ REVISIONS* 1. East Elevation
Original Date: _____ (describe) 2. South Elevation
Original Builder: _____ 3. West Elevation
Is there an HDC survey form for this building attached? Yes N/A 4. North Elevation

*Cloud on drawings and submit photographs of existing elevations.

DETAIL OF WORK TO BE PERFORMED

Foundation: Height Exposed 4" Block Block Parged Brick (type) _____ Poured Concrete Piers
Masonry Chimney: Block Parged Brick (type) _____ Other _____
Roof Pitch: Main Mass 8 /12 Secondary Mass _____ /12 Dormer _____ /12 Other _____
Roofing material: Asphalt: 3-Tab Architectural
 Wood (Type: Red Cedar, White Cedar, Shakes, etc.) RED CEDAR

Fence: Height: _____
Type: _____
Length: _____

Skylights (flat only): Manufacturer N/A Rough Opening _____ Size _____ Location _____
Manufacturer _____ Rough Opening _____ Size _____ Location _____

Gutters: Wood Aluminum Copper Leaders (material) _____

Leaders (material and size): _____

Sidewall: White cedar shingles NATURAL Clapboard (exposure: _____ inches) Front Side
 Other _____

Trim: A. Wood Pine Redwood Cedar Other _____

B. Treatment Paint Natural to weather Other _____

C. Dimensions: Fascia 1 x 8 Rake 1 x 4 Soffit (Overhang) _____ Corner boards _____ Frieze _____

Window Casing 1X4 Door Frame 1X4 Columns/Posts: Round _____ Square _____

Windows*: Double Hung Casement All Wood Other _____

True Divided Lights(muntins), single pane SDL's (Simulated Divided Lights) Manufacturer MARVIN

Doors* (type and material): TDL SDL Front CARRIAGE Rear _____ Side FRENCH

Garage Door(s): Type _____ Material _____

Hardscape materials: Driveways _____ Walkways _____ Walls _____

* Note: Complete door and window schedules are required.

COLORS

Sidewall NATURAL Clapboard (if applicable) _____ Roof NATURAL
Trim NATURAL Sash WHITE Doors WHITE
Deck _____ Foundation _____ Fence _____ Shutters _____

* Attach manufacturer's color samples if color is not from HDC approval list.

I hereby authorize the agent named above to act on my behalf to make changes in the specifications or the plans contained in this application in order to bring the application into compliance with the HDC guidelines. I hereby agree to abide by and comply with the terms and conditions of this application. I hereby agree that the submission of any revisions to this application will initiate a new sixty-day review period.

Date 08/25/2020

Signature of owner of record _____

Signed under penalties of perjury



REQUIRED WITH ALL APPLICATIONS:

- 1. Completed Application Form: Description of ALL work must be indicated on application form.
2. Property Owner's Signature: Current owner's signature preferred; if the agent is signing the application written authorization from the owner (letter, fax, email) must be provided.
3. Application Fee: See back of application for fee schedule or call the office.
4. Locus Map (4 copies): Location Map must include north arrow, parcel boundaries, primary and secondary streets. (Town GIS Map Site) https://www.nantucket-ma.gov/151/GIS-Maps
5. Site Plan (4 Copies): must include the following: lot dimensions, north arrow, all existing structures, proposed work (highlighted) with dimension to lot lines, scale, driveway, grade changes, and placement of HVAC units, electrical boxes, fuel tanks, etc..
6. 8-1/2" x 11" Copies of ALL Application Materials: Must include the following: application form (reduced 64%), locus map, plot plan, all elevations and floor plans, window schedule, photographs, other relevant supporting material. All material MUST BE LEGIBLE (font size no smaller than 12), collated and stapled.
7. Photographs: Required of ALL applications for alterations to an existing structure. Photographs must be clear and labeled with application address or contextual address.
8. Electronic submission: All documents submitted to the HDC office must be emailed to hdcsubmissions@nantucket-ma.gov.

REQUIRED WHERE APPLICABLE:

- 1. Supplemental Information for Historic Buildings: It is the applicant's responsibility to research the historical status of any and ALL buildings. Additional information may be obtained from the Nantucket Historical Association Library. If not historic, denote on application.
2. Exterior Elevations and Floor Plans (4 copies): Must be Y.-inch scale and include all affected sides of the building, cardinal points (N, S, E, W), dimensions, heights, floor and ceiling heights, elevations of finished grade, window details and placement of HVAC units, electrical boxes, fuel tanks, etc. All changes from approved or existing design must be clouded on drawing. All material MUST BE LEGIBLE, collated and stapled. Reduced sets should maintain a font size of 12.
3. As-Built Plans (1copy): of existing elevations
4. Hardscaping Plans (4 copies): To legible scale. This includes fences, decks, porches, arbors, retaining walls, tennis courts, swimming pool, driveways, gazebos etc. All material MUST BE LEGIBLE, collated and stapled.
5. Topographic Map: Must show existing and proposed grade for any change of more than one foot in height on grade. Retaining walls must be applied for separately (see hardscaping plan).
6. Door and Window Schedule (4 copies): Must include window type (true divided, simulated divided), number of lights, dimensions, materials, manufacturers type name and type number.
7. I UNDERSTAND THAT A TRUE DIVIDED LIGHT WINDOW/DOOR IS DEFINED AS MULTIPLE INDIVIDUAL SINGLE PANES OF GLASS (i.e., NOT DOUBLE-PANED OR INSULATED) ASSEMBLED IN THE SASH/DOOR USING MUNTINS.
8. Abutter Notification Materials - Abutters list from Assessors Office, certified mail stubs, and a copy of letter are required for all applications for changes of 1000 square feet or more except in the Nantucket Historic Core and 'Sconset Historic Core where the requirement for new construction is 100 square feet.
9. Approvals from Planning Board, Zoning Board of Appeals, Conservation Commission etc.

TOWN OF NANTUCKET
HISTORIC DISTRICT COMMISSION

LIST OF PARTIES IN INTEREST IN THE MATTER OF THE PETITION OF

PROPERTY OWNER: CANNONBURY HOLDINGS 2, LLC

MAILING ADDRESS: 105 NEWBURY STREET, 4TH FLOOR, BOSTON, MA 02116

PROPERTY LOCATION: 6 SLEETWING CIRCLE

ASSESSORS MAP/PARCEL: MAP 74 PARCLE 24

SUBMITTED BY: ANDREW KOTCHEN - (WORKSHOP/APD)

SEE ATTACHED PAGES

I certify the foregoing is a list of persons who are owners of land directly adjacent to the subject property or directly opposite the subject property on any public or private street or way, all as they appear on the most recent applicable tax list.

8-6-2020

DATE


Digitally signed by Rob Ranney
DN: cn=Rob Ranney, o=Town of
Nantucket, ou=Assessor's Office,
email=rranney@nantucket-ma.gov,
c=US
Date: 2020.08.06 09:05:47 -04'00'

ASSESSOR'S OFFICE
TOWN OF NANTUCKET

CURRENT ZONING CLASSIFICATION:
Sconset Residential 20 (SR-20)

MINIMUM LOT SIZE: 20,000 S.F.
MINIMUM FRONTAGE: 75 FT.
FRONT YARD SETBACK: 30 FT.
REAR/SIDE SETBACK: 10 FT.
GROUND COVER % : 12.5%

PLAN FILE 5-B



GRAPHIC SCALE



(IN FEET)
1 inch = 80 ft.

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Baltimore, MD 21212

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Malley Michael + Awalt Kathleen

Street and Apt. No., or PO Box No.
16 Enfield Rd

City, State, ZIP+4®
Baltimore, MD 21212

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Andover, MA 01810

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Gilmartin Mary J Etal

Street and Apt. No., or PO Box No.
4 Homestead Circle

City, State, ZIP+4®
Andover, MA 01810

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Boston, MA 02116

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Cannonbury Holdings 2 LLC

Street and Apt. No., or PO Box No.
105 Newbury St 4th Fl

City, State, ZIP+4®
Boston, MA 02116

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Dedham, MA 02026

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Hollins Donald + Sheila TRS

Street and Apt. No., or PO Box No.
75 Glenridge Rd

City, State, ZIP+4®
Dedham, MA 02026

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Dedham, MA 02026

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Hollins Donald W + Sheila

Street and Apt. No., or PO Box No.
75 Glenridge Rd

City, State, ZIP+4®
Dedham, MA 02026

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions

U.S. Postal Service™
CERTIFIED MAIL® RECEIPT

Domestic Mail Only

For delivery information, visit our website at www.usps.com™.

Dedham, MA 02026

Certified Mail Fee \$3.55

Extra Services & Fees (check box, add fee as appropriate)
 Return Receipt (hardcopy) \$0.00
 Return Receipt (electronic) \$0.00
 Certified Mail Restricted Delivery \$0.00
 Adult Signature Required \$0.00
 Adult Signature Restricted Delivery \$0.00

Postage \$0.55

Total Postage and Fees \$4.10

0048
06

Postmark
Here

08/07/2020

Sent To
Chisolm Veronica + William II

Street and Apt. No., or PO Box No.
310 Shawmut Ave

City, State, ZIP+4®
Boston, MA 02118

PS Form 3800, April 2015 PSN 7530-02-000-9047 See Reverse for Instructions



HISTORIC DISTRICT COMMISSION

2 Fairgrounds Road

Nantucket, Massachusetts 02554

Telephone: 508.325.7587

Fax: 508.228.7298

NOTICE OF HDC APPLICATION

ABUTTERS AND INTERESTED PARTIES

Please be informed that the Nantucket Historic District Commission will be considering the following proposal:

Address of Proposed Work: 6 Sleetwing Circle

Tax Map Number: 74 Parcel Number: 24

Owner of Record: Cannonbury Holdings 2, LLC

Description of Proposal: New 2 story Dwelling, Garage, Driveway, Shed

Anticipated HDC Submission Date: 08/11/2020

You have been identified either as an abutter or interested party to the above property and are being notified in accordance with the Town Bylaw. Please note that the above submission date is an estimate only; the actual meeting date will be determined once the HDC staff has established that a complete application has been submitted. Please contact the HDC office to verify the date. Please note that notification is only required at the time of initial submission of an application, not for each time an application goes before the Commission. Abutters are responsible for monitoring the status of applications.

If you wish to comment on the above proposal, you are encouraged to submit your comments in writing to the HDC office. If you wish to testify at a Commission meeting please be aware that your testimony may be limited by the Commission in accordance with Commission policies, which are included on the back of this form. Due to the large sizes of most applications, the HDC office may not be able to send faxed copies of the plans. Off-island abutters wishing more detailed information may enlist an on-island representative to view the plans in the HDC office.

If you have any questions, please contact the HDC office at 508.325.7587.

HDC POLICIES FOR AN ABUTTER AND/OR INTERESTED PARTY TESTIMONY

Abutters are encouraged to limit their responses to issues that fall within the statutory mandate of the HDC – mainly the appearance of a proposal from the publicly traveled way and its impact on the existing historic environmental context. Issues such as land uses, noise, and impacts on private property are outside of the HDC’s purview and cannot be addressed by the Commission.

In order to maintain a balance between the wishes of abutters and interested parties to express their concerns and the need of the HDC to conduct its business in a timely fashion, the following policies have been established:

Abutters and interested parties wishing to testify before the Commission shall be limited to three minutes of testimony. Only one representative from each abutting property or interested party shall be permitted to testify.

For those cases in which a substantial number of abutters and/or interested parties wish to testify (as determined by the Chair), the Chair shall structure the review of an application as follows:

1. Introduction of the application;
2. Response by applicant;
3. Public comment in favor of proposal;
4. Public comment in opposition of proposal;
5. Closing of public comment-no further comment unless requested by Commission members through the Chair;
6. Commission comments and discussion with applicant;
7. Commission action.

The above meeting policies may be waived at the discretion of the Chair.

CANNONBURY LANE

CANNONBURY LANE
NANTUCKET, MA 02564



NANTUCKET, MA



CANNONBURY LANE



PROJECT SITE





VIEW 1 - ENTRANCE GATE FROM LOW BEACH ROAD





VIEW 2 - NORTHEND OF CANNONBURY LOOKING SOUTH



BFC GARAGE - LOT 6

BFC

GARAGE - LOT 6

6 Sleetwing Cir
Nantucket, MA 02554

OWNER

CANNONBURY LANE PARTNERS, LLC
105 Newbury Street
Boston, MA 02116

ARCHITECT

WORKSHOP/APD

WORKSHOP/APD ARCHITECTURE DPC
39 W 38th Street, 7th Fl, New York, NY 10018
T: (212) 273-9712 info@workshopapd.com

STRUCTURAL ENGINEER

CRAFT - ENGINEERING STUDIO
39 West 38th Street, 7th Fl
New York, NY 10018
T: (646) 912-9867

LANDSCAPE ARCHITECT

MIROSLAVA AHERN LLC
PO Box 2213
Nantucket, MA 02584
T: (508) 333-5138

SURVEYOR

BLACKWELL & ASSOCIATES, INC.
20 Teasdale Circle
Nantucket, MA 02554
T: (508) 228-9028

CONTRACTOR

BLUEFLAG CONSTRUCTION, LLC
105 Newbury Street, 4th Fl
Boston, MA 02116
T: (508) 257-1325

HDC SUBMISSION


GARAGE - LOT 6

25 AUGUST 2020


6 Sleetwing Cir
Nantucket, MA 02554

PROJECT NO. - 318008

LOCUS PLAN



LOCUS PLAN



NOT TO SCALE

LIST OF DRAWINGS

SHEET	TITLE	ISSUE TYPE	08/25/2020 HDC SUBMISSION
T-000	TITLE SHEET	HDC	■
G-100	GENERAL NOTES	HDC	■
L-100	SITE/LOT PLAN	HDC	■
A-100	FLOOR PLANS	HDC	■
A-101	FLOOR PLANS	HDC	■
A-201	BUILDING ELEVATIONS	HDC	■

ZONING INFORMATION

Map & Parcel	74/24
Current Zoning	SR-20
Minimum Frontage	75 FT.
Front Setback	30 FT.
Side/Rear Setback	10 FT.

Lot Size	22,614 SF
Min. Lot Size	20,000 SF
Allowable G.C.	12.5 %
Max G.C.	2,826.75 SF
Proposed G.C. Dwelling	2,195 SF
Proposed G.C. Garage	404 SF
Total G.C.	2,599 SF

ALL DESIGNS & SPECS ARE SUBJECT TO VERIFICATION OF EXG. FIELD CONDITIONS

REVISIONS

NO.	DESCRIPTION

FOR CONSTRUCTION




ISSUES

NO.	DESCRIPTION
1	08/25/2020 HDC SUBMISSION

CONSTRUCTION DOCUMENTS
DRAWN BY: MLW/IZM
CHECKED BY: T.J.Z
DATE: 01/16/2019
SCALE:
PROJ. NO. 318008

TITLE SHEET

T-000



WINDOW COLOR

SASH : WHITE
TRIM : NATURAL

NO.	DATE	DESCRIPTION



1	08/25/2020	HDC SUBMISSION
2	04/12/2019	DOB PERMIT SET

CONSTRUCTION DOCUMENTS	
DRAWN BY:	MLW/IZM
CHECKED BY:	TJZ
DATE:	09/12/2018
SCALE:	1/4" = 1'-0"
PROJ. NO.	318008

GENERAL NOTES:

- DRAWINGS ARE REPRESENTATIVE DOCUMENTS TO FACILITATE CONSTRUCTION. CONTRACTOR SHOULD FIELD VERIFY ALL DIMENSIONS AND CONDITIONS PRIOR TO CONSTRUCTION. THE HEIGHTS OF GRADE INDICATED ON DRAWINGS ARE APPROXIMATE AND ARE PROVIDED FOR INFORMATION ONLY. NOTIFY DESIGNER OF ANY ALTERATIONS OR DISCREPANCIES IMMEDIATELY UPON DISCOVERY AND BEFORE PROCEEDING WITH WORK.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR DISTRIBUTION OF DRAWINGS TO THE SUB-CONTRACTORS UNDER HIS JURISDICTION.
- THE CONTRACTOR IS TO COORDINATE THE WORK OF ALL SUB-CONTRACTORS INCLUDING THE TIMING AND SCHEDULING OF THEIR WORK AND THE LAYOUT OF THEIR SYSTEMS. THE CONTRACTOR SHALL PROVIDE ALL SUB-CONTRACTORS WITH NECESSARY POWER AND ACCESS AND CONNECTIONS THROUGH FOUNDATION WALLS AS REQUIRED.
- WORKSHOP/APD IS CONTRACTED TO SERVE AS THE OWNER'S REPRESENTATIVE DURING CONSTRUCTION. A REPRESENTATIVE OF WORKSHOP/APD SHALL MAKE PERIODIC SITE VISITS TO VERIFY CONSTRUCTION PROGRESS AND WILL REPORT FINALLY TO THE OWNER AND CONTRACTOR IN THE FORM OF A WRITTEN REPORT. THE CONTRACTOR SHALL PROVIDE FREE ACCESS TO THE WORK TO THE OWNER, ARCHITECT, SUBCONTRACTOR, AND THEIR REPRESENTATIVES AT ALL TIMES.
- THE CONTRACTOR SHALL ACKNOWLEDGE THAT JOB SITES ARE DIFFICULT AND DANGEROUS PLACES TO WORK BY NATURE. AS SUCH, ALL NECESSARY PRECAUTIONS WILL BE TAKEN TO ENSURE THE SAFETY AND GENERAL WELL BEING OF HIS EMPLOYEES. CONTRACTOR SHALL PROVIDE GUARDS, RAILS, BARRICADES, FENCES, CATCH PLATFORMS, BRIDGING, DECKING, NIGHT LIGHTING, ETC. AS REQUIRED. THE USE OF ANY STAIRS AND/OR RADIOS AND THE PRESENCE OF PETS OR ANY KIND ARE PROHIBITED ON THE JOB SITE.
- DRAWINGS SHALL NOT BE SCALED BY HAND. USE ONLY PRINTED DIMENSIONS TO IDENTIFY SIZE AND DIMENSION OF MATERIALS AS SHOWN. CONTACT THE DESIGNER TO VERIFY ANY DIMENSION THAT HAS BEEN OMITTED FROM THESE PLANS.
- CONTRACTOR TO PROVIDE ALL MATERIALS FOR A COMPLETE JOB AS INDICATED IN THE DRAWINGS BOTH GRAPHICALLY AND WRITTEN. IN CASE OF DISCREPANCIES, THE MORE STRINGENT AND/OR COSTLY EXAMPLE SHALL BE ASSUMED, CONSULT DESIGNER IF SUCH A SITUATION OCCURS.
- SHOP DRAWINGS SHALL BE SUBMITTED TO WORKSHOP/DPC PRIOR TO PROCEEDING WITH WORK. FOR ALL MATERIALS THAT REQUIRE FABRICATION WORKSHOP SHALL REVIEW AND RETURN SHOP DRAWINGS TO CONTRACTOR WITHIN A PERIOD OF TEN WORKING DAYS FROM THE DATE OF SUBMITTAL.
- CONTRACTOR SHALL FURNISH SAMPLES OF ALL MATERIALS, AND/OR FINISHES AS SPECIFIED FOR CONSTRUCTION AT THE REQUEST OF THE OWNER OR DESIGNER.
- ALL MATERIALS SHALL BE NEW, UNUSED, AND OF THE HIGHEST QUALITY IN EVERY RESPECT UNLESS NOTED OTHERWISE OR AT THE SPECIFIC AUTHORIZATION OF THE OWNER.
- ALL WORK SHALL BE ERECTED AND INSTALLED PLUMB, LEVEL, SQUARE AND TRUE.
- CONTRACTOR SHALL PERFORM ALL CUTTING AND PATCHING REQUIRED TO COMPLETE WORK OR MAKE PARTS FIT TOGETHER PROPERLY, WITHOUT COMPROMISING QUALITY OF WORK.
- DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR BRACING AND PROTECTING ALL WORK FROM DAMAGE, BREAKAGE, COLLAPSE, DISTORTIONS AND MIS-ALIGNMENT ACCORDING TO APPLICABLE BUILDING CODES AND STANDARDS OF GOOD PRACTICE.
- CONTRACTOR SHALL MAINTAIN AND PROTECT ALL EXISTING SYSTEMS AT ALL TIMES FROM THE EFFECTS OF ADVERSE WEATHER (RAIN, SNOW, COLD, ETC.) AT NO ADDITIONAL COST TO THE OWNER.
- ALL WORK SHALL BE INSTALLED SO THAT REQUIRED PARTS ARE READILY ACCESSIBLE AND AVAILABLE FOR INSPECTION, OPERATION, MAINTENANCE AND REPAIR.
- CONTRACTOR SHALL MAINTAIN CLEAR AND UNOBSTRUCTED ACCESS FROM ALL FLOORS TO STAIRWELLS AND EXTERIOR EXITS AT ALL TIMES.
- CONTRACTOR SHALL HAVE SOLE RESPONSIBILITY FOR PROTECTING ALL DANGEROUS AREAS FROM ENTRY BY UNAUTHORIZED PARTIES.
- CONTRACTOR SHALL PROVIDE PROTECTION OF ALL WINDOWS AND DOORS DURING CONSTRUCTION. MEANS OF PROTECTION SHALL NOT BE ATTACHED TOWINDOW AND DOOR FRAMES.
- THE CONTRACTOR AND EACH SUBCONTRACTOR SHALL BE REQUIRED TO COORDINATE WITH OTHER SUBCONTRACTORS AS NECESSARY, INCLUDING THOSE HIRED UNDER SEPARATE CONTRACT BY THE OWNER. EACH SUBCONTRACTOR SHOULD COMPLETE WORK ON AN EXPEDIENT AND REASONABLE SCHEDULE, IN A MANNER THAT DOES NOT DELAY OTHER TRADES AND SUBCONTRACTORS FROM COMPLETION OF WORK.
- ALL NAILS AND FASTENERS IN AREAS PRONE TO MOISTURE SHALL BE "HOT DIPPED GALVANIZED" UNLESS NOTED OTHERWISE.
- THE CONTRACTOR SHALL KEEP SUFFICIENT WORKMAN ON THE JOB SITE AT ALL TIMES TO PERFORM WORK IN THE MOST EXPEDITIOUS MANNER CONSISTENT WITH GOOD WORKMANSHIP, SOUND BUSINESS PRACTICE AND IN THE BEST INTEREST OF THE OWNER.
- THE CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS AND INSPECTION SERVICES OF LOCAL AUTHORITIES OTHER THAN THE ACTUAL BUILDING PERMIT AND HISTORIC DISTRICT COMMISSION APPROVAL, WHICH SHALL BE SECURED BY THE OWNER OR DESIGNER PRIOR TO THE SCHEDULED START DATE. ALL INSPECTIONS, RECORDS AND CERTIFICATES OF OCCUPANCY SHALL BE GIVEN TO THE OWNER AT THE END OF THE JOB. THE JOB SHALL NOT BE CONSIDERED COMPLETE UNTIL THE CERTIFICATE OF OCCUPANCY IS ISSUED.
- ALL WORK SHALL CONFORM TO ALL APPLICABLE NATIONAL, STATE AND LOCAL BUILDING, PLUMBING, ELECTRICAL, AND LIFE SAFETY CODES, EVEN WHEN NOT SPECIFIED IN THE DRAWING, NOTES, OR SPECIFICATIONS. IF ANY CODE IS IN CONFLICT WITH THESE, THE CONTRACTOR SHALL REPORT SUCH TO CWA FOR REVISIONS PRIOR TO BIDDING. IN THE EVENT OF CONFLICT BETWEEN APPLICABLE CODES OR REGULATIONS AND REFERENCE STANDARDS OF THESE PLANS AND SPECIFICATION, THE MORE STRINGENT PROVISIONS SHALL GOVERN.
- THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING UTILITY COMPANIES TO ENSURE SAFE DIGGING.
- A REGISTERED SURVEYOR SHALL BE REQUIRED TO SET ALL FOUNDATION CORNERS, ELEVATIONS AND DIMENSIONS ON SITE.
- USE OF THESE DRAWINGS MUST BE IN COMPLIANCE WITH ALL OCCUPATIONAL SAFETY & HEALTH ADMINISTRATION (OSHA) REQUIREMENTS.

FOUNDATION NOTES:

- FOUNDATION NOTES ARE APPLICABLE TO ALL CONDITIONS UNLESS OTHERWISE NOTED.
- ALL FOUNDATION WALLS SHALL BE 10" THICK CONCRETE, MINIMUM 3000PSI AT 28 DAYS, UNLESS OTHERWISE NOTED.
- FOUNDATION WALLS SHALL BE KEVED INTO FOOTINGS.
- FOOTINGS SHALL BE A MINIMUM OF 1'-0" X 2'-0" W/ WITH 3-#4 CONTINUOUS HORIZONTAL BARS. HORIZONTAL REINFORCING SHALL BE PLACED AT 3" ABOVE BOTTOM OF FOOTING.
- ALL FOOTINGS AND CONCRETE PIERS SHALL EXTEND 4'-0" BELOW GRADE MINIMUM.
- CONCRETE PIERS SHALL HAVE BELL CAST FOOTING. BASE OF BELL SHALL BE 3 TIMES WIDTH OF PIER; DEPTH OF BELL SHALL EQUAL WIDTH OF PIER. TAPER OF BELL SHALL BE 45 DEG. ANGLE MINIMUM.
- ALL PERIMETER FOUNDATION WALLS SHALL HAVE WATERPROOFING APPLIED TO THE EXTERIOR.
- FOUNDATION WALLS SHALL INCORPORATE 16" LONG - 1/2" DIAMETER ANCHOR BOLTS AT 32" O.C. MINIMUM, ON ALL PERIMETER WALLS. A MINIMUM OF WDOH BOLTS SHALL BE USED AT EACH SILL PLATE. HOLD BOLTS 18" OFF CORNERS MINIMUM. APPROVAL OF TOP SOIL REMOVAL SHALL BE IN THE FORM OF EXCHANGE ORDER.
- CONCRETE FLOOR SLABS SHALL BE 4" THICK MINIMUM AND BE REINFORCED WITH WELDED WIRE MESH OR FIBER MESH REINFORCING. REINFORCING SHALL BE PLACED AT THE CENTER OF THE SLAB. FLOOR SLABS SHALL BE POURED OVER 4" GRAVEL BASE AND 6 MIL. POLY-VAPOR BARRIER ON STRUCTURALLY COMPACTED OR UNDISTURBED SOIL.
- CONTRACTOR AND SUBCONTRACTORS SHALL USE CLEAN SAND, WELL GRADED AND FREE FROM ANY DELETERIOUS SUBSTANCES, AND CLEAN WATER, TAKEN FROM A SOURCE SUITABLE FOR DOMESTIC CONSUMPTION.
- FOR ALL BRICK OR STONE FINISHES THE CONTRACTOR SHALL SUBMIT A SAMPLE TO THE DESIGNER FOR APPROVAL PRIOR TO INSTALLATION.
- ANCHORS AND TIES SHALL BE CORROSION PROOF AND GALVANIZED AFTER FABRICATION.
- COLD WEATHER INSTALLATIONS FOR CONCRETE, WHEN AIR TEMPERATURE IS BELOW 40 DEGREES F, REQUIRE APPROVAL BY THE DESIGNER.
- MASONRY WORK SHALL BE PLUMB, TRUE TO LINE, WITH COURSES LEVEL. BUILD IN ALL METAL TIES AND ANCHORS AS WORK PROGRESSES.
- CONCRETE MASONRY UNIT CONSTRUCTION SHALL COMPLY WITH THE FOLLOWING STANDARDS: HOLLOW UNITS - ASTM C-90; SOLID UNITS - ASTM C-145; PORTLAND CEMENT - ASTM C-150; MASONRY CEMENT - ASTM C-91 (NON-STAINING CEMENT SHALL BE USED WHERE NON-STAINING MORTAR IS REQUIRED); MORTAR - ASTM C-207. 6. C.M.U., BOTH BOTTOM AND ENDS, SHALL BE SET IN A FULL BED OF MORTAR WITH JOINTS OF UNIFORM THICKNESS AND HEAD JOINTS IN ALTERNATE COURSES PLUMB OVER THE ONES BELOW.
- ALL JOINTS SHALL BE TOoled AS SOON AS POSSIBLE AFTER INITIAL SET. FLUSH JOINTS SHALL NOT BE PERMITTED.
- REFER TO DETAILS FOR FURTHER INFORMATION.

PLUMBING/MECHANICAL NOTES:

- STRUCTURAL MEMBERS SHALL NOT BE IMPAIRED OR UNDERMINED BY IMPROPER CUTTING OR DRILLING.
- ALL PLUMBING/MECHANICAL WORK SHALL COMPLY WITH ALL APPLICABLE CODES, BE PERFORMED BY A LICENSED TRADESPERSON, AND BE COMPLETED IN ACCORDANCE WITH THE DIRECTION OF LOCAL BUILDING CODE OFFICIALS. SUBCONTRACTORS AND TRADESPERSONS ARE RESPONSIBLE FOR OBTAINING REQUIRED PERMITS FOR THEIR TRADE, SCHEDULING AND COMPLETING REQUIRED INSPECTIONS AND OPERATING ON A REASONABLE AND EFFICIENT SCHEDULE THAT DOES NOT DELAY THE WORK OF OTHER TRADES.
- ALL MATERIALS SHALL BE SIZED IN ACCORDANCE WITH THE PROPOSED PLANS, ALLOWING FOR FUTURE EXPANSION IF INDICATED. ALL WORK SHALL BE INSTALLED SO THAT REQUIRED PARTS ARE READILY ACCESSIBLE AND AVAILABLE FOR INSPECTION, OPERATION, MAINTENANCE AND REPAIR.
- ALL PRODUCTS, MATERIALS AND FIXTURES SHALL BE INSTALLED IN A MANNER CONSISTENT WITH SOUND PRACTICE AND QUALITY WORKMANSHIP.
- PLUMBING WORK SHALL INCLUDE ALL LABOR AND MATERIALS FOR ALL PIPING, FIXTURES, HOT WATER HEATER, AND SEWER/SEPTIC CONNECTIONS. THIS INCLUDES CONNECTIONS FOR AN ICEMAKER IN THE REFRIGERATOR, THE DISHWASHER, AND WASHING MACHINE AS INDICATED ON PLANS. THE KITCHEN SINK WILL HAVE A GARBAGE DISPOSAL.
- HOT WATER HEATER SHALL BE PROPANE FIRED HOT WATER HEATER, POWER VENTED, 45 GALLON CAPACITY ("SUPER STORE" OR APPROVED EQUIVALENT).
- PLUMBER SHALL FURNISH AND INSTALL 500 GAL. UNDERGROUND PROPANE STORAGE TANK, AND ALL REQUIRED PIPING TO BOILER, CLOTHES DRYER AND KITCHEN RANGE.
- HEATING WORK SHALL INCLUDE ALL LABOR AND MATERIALS, ELECTRICAL/PLUMBING CONNECTIONS, AND INSTALLATION AS THEY OCCUR. DESCRIPTION OF SPECIFIC UNIT SHALL BE PART OF THE BID. STANDARD HEATING UNIT SHALL BE PROPANE FIRED RADIANT HOT WATER BASEBOARD SYSTEM WITH EFFICIENCY RATING OF 94 UNIT IS TO BE SIDEWALL VENTED. UNIT SIZE SHALL BE SIZED TO ACCOMMODATE ALL EXTERIOR WALLS.
- TEMPERATURE, HEATING SYSTEM SHALL BE CAPABLE OF OPERATING AT PEAK EFFENCY AT A TEMPERATURE OF 72°F. HEATING SYSTEM SHALL BE DIVIDED INTO WHO ZONES. THERMOSTATS SHALL BE DIGITAL AND PROGRAMMABLE.
- VENT TO THE EXTERIOR ALL BATHROOMS WHICH DO NOT HAVE OPERABLE WINDOWS.

FRAMING NOTES:

- ALL WOOD FRAMING MEMBERS SHALL BE STRUCTURAL GRADE #2 OR BETTER.
- ALL WOOD SHALL COMPLY WITH THE U.S. DEPARTMENT OF COMMERCE AMERICAN LUMBER STANDARDS SIMPLIFIED PRACTICE AND GRADING REQUIREMENTS OF A RECOGNIZED ASSOCIATION UNDER WHOSE RULES THE LUMBER IS PRODUCED.
- WOOD SHALL BE FROM LIVE STOCK, THOROUGHLY SEASONED, WELL MANUFACTURED AND GENERALLY FREE FROM WARPAGE THAT CANNOT BE CORRECTED BY BRIDGING OR NAILING.
- MOISTURE CONTENT OF LUMBER SHALL NOT EXCEED 19 % AT THE TIME OF CONSTRUCTION.
- ALL PLAN DIMENSIONS ARE TO OUTSIDE OF FRAMING MEMBERS AND CENTERLINE OF OPENINGS. VERIFY ALL ROUGH OPENINGS WITH WINDOW AND DOOR SCHEDULE.
- ALL EXTERIOR WALLS, AND INTERIOR PARTITION WALLS BEHIND TOILETS, SHALL BE 2X8" STUD CONSTRUCTION AT 16" O.C. TYPICAL. ALL OTHER INTERIOR PARTITION WALLS SHALL BE 2X4" STUD CONSTRUCTION AT 16" O.C. TYPICAL. WALLS SHALL HAVE SINGLE SHDIE AND DOUBLE TOP PLATE.
- JOIST HANGARS SHALL BE USED AT ALL FLUSH-FRAMED FLOOR JOISTS. JOISTS OVERLAPPING AT A SUPPORTING BEAM, SHALL OVERLAP 3" MINIMUM.
- PROVIDE WOOD BLOCKING OR METAL BRIDGING AT 1/3RD POINTS ON ALL FLOOR JOISTS. BLOCKING SHOULD BE SPACED 4'-0" O.C. MINIMUM AND 8'-0" O.C. MAXIMUM.
- DOUBLE FLOOR JOISTS OR BLOCKING SHALL BE PROVIDED BELOW ALL INTERIOR PARTITION WALLS.
- SIZES OF WOOD MEMBERS ARE NOMINAL SIZES. ALL LUMBER SHALL BE SURFACED ON FOUR SIDES, UNLESS NOTED OTHERWISE.
- STRUCTURAL MEMBERS SHALL NOT BE IMPAIRED OR UNDERMINED BY IMPROPER CUTTING OR DRILLING.
- INSTALL GIRDER MEMBERS WITH JOINTS OVER SUPPORTS, PROVIDE 1/2" AIRSPACE AT ENDS AND SIDES OF GIRDERS FRAMED INTO MASONRY OR CONCRETE. WOOD SHIMS UNDER THE ENDS OF GIRDERS SHALL NOT BE PERMITTED.
- MINIMUM BEARING OF JOISTS FRAMED INTO MASONRY SHALL BE 3".
- JOISTS EXTENDING OVER BEARING PARTITIONS OR BEAMS MAY BE BUTTED AND TIED TOGETHER, OR NAILED TOGETHER WITH A MINIMUM OVERLAP OF 4".
- EXTERIOR AND BEARING WALL CONSTRUCTION SHALL INCLUDE ADEQUATE RESISTANCE TO WRACKING BY THE USE OF CORNER BRACING OR ANCHORAGE OF STRUCTURAL SHEATHING TO PLATES.
- JAMB STUDS, EXTENDING IN ONE PIECE FROM HEADER TO SOLE PLATE, SHALL BE INSTALLED AT ALL WINDOW AND DOOR OPENINGS TO FORM RIGID ENCLOSURE.
- PLYWOOD SHALL COMPLY WITH ALL APPLICABLE STANDARDS OF THE APA (AMERICAN PLYWOOD ASSOCIATION).
- EXTERIOR TYPE HARDWOOD PLYWOOD, "TECHNICAL" OR "TYPE 1", MAY BE USED FOR ANY PART OF THE STRUCTURE.
- STRUCTURAL INTERIOR TYPE, "STRUC-INT", PLYWOOD MAY BE USED FOR ALL INTERIOR WORK AND EXTERIOR WORK NOT DIRECTLY EXPOSED TO THE WEATHER.
- INTERIOR PLYWOOD, "INT" OR "TYPE 2" MAY BE USED FOR INTERIOR WORK, EXCEPT BATHROOM AND SHOWER ENCLOSURES.
- ROOF SHEATHING: 3/4" EXTERIOR GRADE T&G "TECHNICAL" PLYWOOD NAILED AT 10" O.C. WITH GALVANIZED 100 COMMON NAILS.
- FLOOR SHEATHING: 3/4" STRUCTURAL "STRUCT-INT" PLYWOOD NAILED AT 10" O.C. WITH 100 COMMON NAILS.
- EXTERIOR WALL SHEATHING: 1/2" EXTERIOR GRADE "TECHNICAL" PLYWOOD NAILED AT 6" O.C. WITH GALVANIZED 60 COMMON NAILS.
- ALL OTHER SHEATHING: 1/2" INTERIOR GRADE "INT" PLYWOOD NAILED AT 6" O.C. WITH 60 COMMON NAILS.
- FRAME ALL RAFTERS OPPOSITE EACH OTHER AT RIDGE WITH TIES OR RIDGE BOARD. THE DEPTH OF THE RIDGE BOARD SHALL BE NO LESS THAN THE CUT OF THE RAFTERS.

EXTERIOR FINISH NOTES:

- BUILDING PAPER SHALL BE INSTALLED OVER ALL EXTERIOR SHEATHING TO RESIST MOISTURE AND WIND INFILTRATION. WALLS SHALL HAVE MINIMUM 15# FELT PAPER. ROOFS SHALL HAVE MINIMUM 30# ASPHALT IMPREGNATED FELT PAPER, WITH NOT LESS THAN 4" OVERLAP. FELT SHALL CONTINUE BEHIND ALL EXTERIOR TRIM, DOUBLED AND FOLDED INTO OPENINGS.
- PROMPTLY REMOVE ALL MANUFACTURERS' STICKERS FROM GLASS AFTER INSTALLATION.
- KEEP AREAS TO BE INSULATED CLEAN AND DRY. DO NOT INSTALL INSULATION WHERE IT MAY BE EXPOSED TO WATER. INSTALL AS PER MANUFACTURERS' INSTRUCTIONS AND BUILDING CODE REQUIREMENTS. PROVIDE INSECT SCREEN OR BARRIER AT ALL VENT OPENINGS.
- EXTERIOR FOUNDATION TO BE PARGE.
- DECKS SHALL USE 1" X 4" MAHOGANY, CONFIRM, LAID FLAT WITH 1/4" REGULAR SPACING. ALL FLOORING AND DECKING SHALL BE TREATED % BOILED LINESOOD OIL 50 % CURPROL AND WITH A MIXTURE OF 50 TRAFIC SHALL BE PREVENTED OVER FINISHED SURFACES FOR THE PERIOD OF ONE WEEK.
- EXTERIOR STEPS SHALL BE EQUAL TO DECK CONSTRUCTION, TRIM AND FINISH. RISERS SHALL MATCH TRIM MATERIAL. NOSING SHALL PROJECT 3/4".
- ALL EXTERIOR STEPS SHALL LAND ON TO A 4" CONCRETE PAD SET ON A 4" GRAVEL BASE ON STRUCTURALLY COMPACTED SOIL. PAD SHALL BE 6" WIDER THAN STEPS AND PROJECT FROM LAST RISER 6" TOWARD DECK AND 18" AWAY FROM DECK.
- PORCH CEILINGS SHALL BE 1X8 CEDAR NATURAL TO WEATHER, SQUARE GROVE.
- PORCH POSTS SHALL BE 4X4 STRUCT. CORE WRAPPED W/ 5 1/4" SQ. NATURAL CEDAR TRIM.
- SIDEWALL SHINGLES SHALL HAVE A MAXIMUM EXPOSURE OF 5", WITH DOUBLED SHINGLES AT ALL EAVES AND STARTER COURSE. BUTTS OF THE SHINGLES SHALL PROJECT 1 1/2" MINIMUM FROM THE EDGE OF THE ROOF EAVES TO ENSURE PROPER SHILLAGE.
- ALL EXTERIOR STEPS SHALL LAND ON TO A 4" CONCRETE PAD SET ON A 4" GRAVEL BASE ON STRUCTURALLY COMPACTED SOIL. PAD SHALL BE 6" WIDER THAN STEPS AND PROJECT FROM LAST RISER 6" TOWARD DECK AND 18" AWAY FROM DECK.
- MASONRY WORK SHALL BE PLUMB, TRUE TO LINE, WITH COURSES LEVEL. BUILD IN ALL METAL TIES AND ANCHORS AS WORK PROGRESSES.
- A CONTINUOUS RIDGE VENT SHALL BE PROVIDED AT ALL ROOF RIDGES, WHERE REQUIRED. SOFFIT VENTING SHALL BE PROVIDED AS INDICATED ON DETAIL DRAWINGS.
- WINDOW STEP FLASHING AT ALL CHIMNEY LOCATIONS.
- SIDEWALL SHALL BE WHITE CEDAR SHINGLES, GRADE B. SHINGLES SHALL BEAR THE OFFICIAL GRADE MARKED LABEL OF THE CEDAR SHINGLE BUREAU.
- CEDAR SHINGLES SHALL HAVE NATURAL FINISH.
- CEILING VENTS SHALL BE "CORE VENT" OR EQUAL, EXTENDING ALONG ALL RIDGE LINES. TERMINATE RIDGE VENTS 12" FROM END OF RIDGE. COVERED W/ SHINGLES.
- EXTERIOR TRIM SHALL BE SPECIFIED AS FOLLOWS:
 - WINDOW AND DOOR JAMBS: 1X5" RED CEDAR WINDOW AND DOOR HEADS: 5/4"X4" RED CEDAR, EXTENDED 3/4" BEYOND JAMB CASING. HEADS TO HAVE CONTINUOUS COPPER DRIP CAP.
 - WINDOW SILLS: WHEN NOT WOOD BY MANUFACTURER SHALL BE PRIMED PINE 2X2 W/ 7D TOP BEVEL EXTENDED 3/4" BEYOND JAMB CASING.
 - DOORSILLS: INSTALLED BY MANUFACTURER
 - CORNER BOARDS: 6" EA. WY. RED CEDAR (IF APPLICABLE)
 - RAKE BOARDS: 1X8 RED CEDAR
 - FASCIA BOARDS: 1X8 RED CEDAR
 - RAKE/FASCIA TRIM BOARDS: 1X3 RED CEDAR
 - FRIEZE BOARDS TO BE 1X6 BLOCKED OUT 1 1/2" TO ACCOMMODATE SOFFIT VENTING & TOP OF SHINGLES (IF APPLICABLE)
 - ALL TRIM TO BE: NATURAL
- ALL EXTERIOR TRIM SHALL BE PAINTED: QUAKER GREY
- ALL EXTERIOR TRIM SHALL BE PAINTED ON ALL FOUR SIDES AND HAVE SQUARED EDGES.
- WINDOW & DOOR MANUFACTURERS AND SIZES AND HARDWARE SHALL BE SPECIFIED IN DOOR AND WINDOW SCHEDULE.
- INSULATION SHALL BE SPECIFIED AS FOLLOWS:
 - EXTERIOR WALLS: 9" R-21 BATT INSULATION, INSTALL 4 MIL. POLY-VAPOR BARRIER AT INSIDE FACE OF ALL EXTERIOR WALLS.
 - ROOF: 9 1/4" R-38 BATT INSULATION, INSTALL 4 MIL. POLY-VAPOR BARRIER AT INSIDE FACE OF ALL EXTERIOR WALLS
 - INTERIOR WALLS AND CEILINGS: USG 9" TERMAFIBER SOUND ATTENUATION BLANKETS
 - FOUNDATION INSULATION: 4" RIGID INSULATION SECURED TO EXTERIOR FACE OF WALL
 - FIRST FLOOR INSULATION: 9 1/4" R-30 BATT INSULATION
- CAVITIES SHALL SUPPORT PROPER VENTING, INCLUDING THE INSTALLATION OF BAFFLES BEWODHEEN ALL RAFTERS. KEEP ALL VENTILATION SPACE UNOBSTRUCTED.
- EXTERIOR BRICK SHALL MEET STANDARDS OF THE BRICK INSTITUTE OF AMERICA (BIA) FOR EXTERIOR/SEVERE WEATHER USE.


GLAZING NOTES:

- IT IS THE CONTRACTOR'S RESPONSIBILITY TO MAKE ALL GLAZING (WINDOW, DOOR, OR OTHERWISE) ADJACENT TO A WALKING SURFACE, STAIR, LANDING, TUB OR SHOWER SAFETY LAMINATED GLASS MEETING THE REQUIREMENTS OF THE MASSACHUSETTS STATE BUILDING CODE, NANTUCKET, AND ANY OTHER APPLICABLE LOCAL OR NATIONAL CODE.
- PROVIDE SHOWER ENCLOSURES AS INDICATED ON THE PLANS. GLASS TO BE LOW IRON, CLEAR GLASS.


ABBREVIATIONS

ABOVE FINISHED FLOOR	AFF	MATERIAL	MATL.
ACCESS PANEL	A.P.	MAXIMUM	MAX.
ACOUSTICAL	ACOUS.	MECHANICAL	MECH.
ADJACENT	ADJ.	METAL	MTL.
AIR CONDITIONING	AL	MINIMUM	MIN.
ALUMINUM	AL	MISCELLANEOUS	MISC.
APPROXIMATE	APPROX.	MOLDING	MLDG.
ARCHITECTURAL	ARCH.	MOUNTED	MTD.
BLOCKING	BLKG	MULLION	MUL.
BY OTHER/OWNER	B.O.	NOMINAL	NOM.
CEILING	CLG.	NOT APPLICABLE	N.A.
CEILING HEIGHT	C.H.	NOT IN CONTRACT	N.I.C.
CENTER LINE	CL.	NUMBER	NO.
CERAMIC TILE	CL.	ON CENTER	O.C.
COLUMN	COL	OPENING	OPNG
CONCRETE	CONC.	OPPOSITE/OPOSITE HAND	OPP./OPH
CONSTRUCTION	CONST.	PAINTED	PTD.
CONTINUOUS	CONT.	PARTITION	PARTN.
DETAIL	DTL.	PLASTER	PL.
DIMENSION	DIM.	PLASTIC LAMINATE	PLAM
DOOR	DR.	PLYWOOD	PLYWD., PLY.
DOUBLE	DOUB.	QUANTITY	QTY.
DOWN	DN.	RECESSED	REC.
DRAINING	DRNG.	REQUIRED	REQD.
EACH	EA.	RETURN AIR	R.A.
ELECTRIC/ELECTRICAL	ELEC.	REVISE/REVISION	REV.
ELEVATION	ELEV.	ROUGH OPENING	R.O.
EMERGENCY	EMER.	SCHEDULE	SCHED.
EQUAL	EQU.	SECTION	SECT.
EQUIPMENT	EQPT.	SHEET	SHI.
EXISTING	EXIST.	SIMILAR	SIM.
EXTERIOR	EXT.	SOLID CORE	SC
FINISH	FIN.	SQUARE FOOT	SQ.FT.
FINISH FLOOR	FIN. FL.	STAINLESS STEEL	S.STL.
FIREPROOF	FRF.	STANDARD	STD.
SELF-CLOSING	S.C.	STEEL	STL.
FLOOR	FL.	STORAGE	STOR.
FLOURESCENT	FLUOR.	TELEPHONE	TEL.
FOOR/FEET	FT.	TO BE DETERMINED	T.B.D.
GLASS	GL.	TYPICAL	TYP.
GRILLE	GRL.	UNLESS OTHERWISE NOTED	U.O.N.
GROUND FAULT INTER.	GFI.	VERIFY IN FIELD	V.I.F.
GYPSTUM WALLBOARD	GWB.	VENT. COMPOSITION TILE	VT/VCT
HANDRAIL	HNDRL.	WITH	W/.
HARDBOARD	HDBD.	WITHOUT	W/O.
HARDWOOD	HWOD.	WOOD	WO.
HEATING, VENT. & A/C	HVAC		
HOLLOW CORE	HC		
HOLLOW METAL	H.M.		
HORIZONTAL	HORIZ.		
INCHES	IN.		
INSULATION	INSUL.		
JUNCTION BOX	J.B.		
LAMINATE	LAM.		
LOW VOLTAGE	L.V.		


REFERENCE SYMBOLS




DRAWING SYMBOLS




MATERIAL SYMBOLS




IDENTIFICATION SYMBOLS



WINDOW LEGEND



EXTERIOR DOOR LEGEND



ALL DESIGNS & SPECS ARE SUBJECT TO
VERIFICATION OF EXG. FIELD CONDITIONS

REVISIONS

NO.	DESCRIPTION

FOR CONSTRUCTION




ISSUES

NO.	DATE	DESCRIPTION
1	08/25/2020	HDC SUBMISSION

DRAWING INFO


CONSTRUCTION DOCUMENTS	
DRAWN BY:	Author
CHECKED BY:	Checker
DATE:	10/26/17
SCALE:	
PROJ. NO.	318008

SITE/LOT PLAN




4 & 6 SWEETWING CIRCLE


SCALE 1/16" = 1'-0"




1 EAST ELEVATION
1/4" = 1'-0"



2 NORTH ELEVATION
1/4" = 1'-0"



3 WEST ELEVATION
1/4" = 1'-0"



4 SOUTH ELEVATION
1/4" = 1'-0"

ALL DESIGNS & SPECS ARE SUBJECT TO
VERIFICATION OF EXG. FIELD CONDITIONS

REVISIONS

NO.	DATE	DESCRIPTION

FOR CONSTRUCTION



ISSUES

NO.	DATE	DESCRIPTION
1	08/25/2020	HDC SUBMISSION

DRAWING INFO

CONSTRUCTION DOCUMENTS
DRAWN BY: MLW/IZM
CHECKED BY: T.JZ
DATE: 09/12/2018
SCALE: 1/4" = 1'-0"
PROJ. NO. 318008

BUILDING ELEVATIONS

ALL DESIGNS & SPECS ARE SUBJECT TO
VERIFICATION OF EXG. FIELD CONDITIONS

REVISIONS

NO.	DESCRIPTION

FOR CONSTRUCTION



ISSUES


NO.	DATE	DESCRIPTION
1	08/25/2020	HDC SUBMISSION

DRAWING INFO


CONSTRUCTION DOCUMENTS
DRAWN BY: MLW/IZM
CHECKED BY: T.JZ
DATE: 09/04/2018
SCALE: 1/4" = 1'-0"
PROJ. NO. 318008

FLOOR PLANS


A-100



3 FOUNDATION
1/4" = 1'-0"



2 FIRST FLOOR
1/4" = 1'-0"



1 ROOF PLAN
1/4" = 1'-0"