ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Tuesday, January 23, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* **Comments:**
Project Number:
Sampled By: *Johnson*
Lab Order Number: *WW-180085*
Date Received: *01/17/18*

Sample Type	Sample Time	Sample Date	Comments			
Y.C. Discharge A	08:15	01/17/18	Yacht Club Discharge			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	0.96	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/17/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/17/18	RL	EPA 300.0
Total Nitrogen	mg/L	0.96	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	0.027	0.005	01/17/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/18/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
Y.C. Opposite Side B	08:23	01/17/18	Y.C. Opposite Side			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	0.64	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/17/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/17/18	RL	EPA 300.0
Total Nitrogen	mg/L	0.64	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	0.010	0.005	01/17/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	0.005	0.005	01/18/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
South Beach St C	08:38	01/17/18	South Beach St MH			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	60	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	0.60	0.01	01/17/18	RL	EPA 300.0
Nitrite-N	mg/L	0.117	0.006	01/17/18	RL	EPA 300.0
Total Nitrogen	mg/L	61	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	7.20	0.005	01/17/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	3.93	0.005	01/18/18	MC	SM 4500-P

BRL=below reportable limits

**see attached*

By: Ronald J. Saari
Ronald J. Saari
Laboratory Director

ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Tuesday, January 23, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* **Comments:**
Project Number:
Sampled By: *Johnson*
Lab Order Number: *WW-180085*
Date Received: *01/17/18*

Sample Type	Sample Time	Sample Date	Comments			
Easy St. Bulkhead D	08:52	01/17/18	Easy Street Bulkhead			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	0.76	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/17/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/17/18	RL	EPA 300.0
Total Nitrogen	mg/L	0.76	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	0.005	0.005	01/17/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/18/18	MC	SM 4500-P

BRL=below reportable limits

**see attached*

By: _____
Ronald J. Saari
Laboratory Director

ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Wednesday, January 24, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* ***Comments:***
Project Number:
Sampled By: *C Johnson*
Lab Order Number: *WW-180088*
Date Received: *01/18/18*

Sample Type	Sample Time	Sample Date	Comments			
Y. C. Disharge A	08:08	01/18/18	Yacht Club Disharge			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/18/18	LL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/18/18	LL	EPA 300.0
Total Nitrogen	mg/L	<0.60	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/18/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
Y.C. Opposite B		08:17	Yacht Club Opposite			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/18/18	LL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/18/18	LL	EPA 300.0
Total Nitrogen	mg/L	<0.60	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/18/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
South Beach St C	08:33	01/18/18	South Beach St M.H.			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	62	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	0.78	0.01	01/18/18	LL	EPA 300.0
Nitrite-N	mg/L	0.198	0.006	01/18/18	LL	EPA 300.0
Total Nitrogen	mg/L	63	NA	01/19/18	KB	Calculation
Total Phosphorous (P)	mg/L	6.12	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	5.36	0.005	01/18/18	MC	SM 4500-P

BRL=below reportable limits

****see attached***

By:
Ronald J. Saari
Laboratory Director

ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Wednesday, January 24, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* **Comments:**
Project Number:
Sampled By: *C Johnson*
Lab Order Number: *WW-180088*
Date Received: *01/18/18*

Sample Type	Sample Time	Sample Date	Comments			
Easy St. Bulkhead D	08:48	01/18/18	Easy Street Bulkhead			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/18/18	LL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/18/18	LL	EPA 300.0
Total Nitrogen	mg/L	<0.6	NA	01/24/18	LL	Calculation
Total Phosphorous (P)	mg/L	0.011	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/18/18	MC	SM 4500-P

BRL=below reportable limits

**see attached*

By: _____
Ronald J. Saari
Laboratory Director

ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Tuesday, January 23, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* **Comments:**
Project Number:
Sampled By: *C Johnson*
Lab Order Number: *WW-180098*
Date Received: *01/19/18*

Sample Type	Sample Time	Sample Date	Comments			
Y.C. Discharge A	08:32	01/19/18	Yacht Club Discharge			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/19/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/19/18	RL	EPA 300.0
Total Nitrogen	mg/L	<0.6	NA	01/22/18	RL	Calculation
Total Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
Y.C. Opposite B	08:37	01/19/18	Yacht Club Opposite			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/19/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/19/18	RL	EPA 300.0
Total Nitrogen	mg/L	<0.6	NA	01/22/18	RL	Calculation
Total Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P
Sample Type	**Sample Time**	**Sample Date**	**Comments**			
South Beach St C	08:51	01/19/18	South Beach St MH			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	61	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	0.52	0.01	01/19/18	RL	EPA 300.0
Nitrite-N	mg/L	0.107	0.006	01/19/18	RL	EPA 300.0
Total Nitrogen	mg/L	62	NA	01/22/18	RL	Calculation
Total Phosphorous (P)	mg/L	6.52	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	6.41	0.005	01/19/18	MC	SM 4500-P

BRL=below reportable limits

**see attached*

By: _____
Ronald J. Saari
Laboratory Director

ENVIROTECH LABORATORIES, INC.
MA CERT. NO.: M-MA 063

8 Jan Sebastian Drive
Sandwich, MA 02563
(508)888-6460 1-800-339-6460
FAX (508)888-6446

Tuesday, January 23, 2018

Sarian Company
8 Jan Sebastian Dr, Unit 24
Sandwich MA 02563

ProjectName: *Nantucket Sewer Investigation* **Comments:**
Project Number:
Sampled By: *C Johnson*
Lab Order Number: *WW-180098*
Date Received: *01/19/18*

Sample Type	Sample Time	Sample Date	Comments			
Easy St. Bulkhead D	09;02	01/19/18	Easy Street Bulkhead			
Parameters	**Units**	**Test Results**	**Reportable Limits**	**Date Analyzed**	**Analyst**	**Method**
Kjeldhal Nitrogen	mg/L	BRL	0.60	01/19/18	KB	SM4500-Norg B-C
Nitrate-N	mg/L	BRL	0.01	01/19/18	RL	EPA 300.0
Nitrite-N	mg/L	BRL	0.006	01/19/18	RL	EPA 300.0
Total Nitrogen	mg/L	<0.6	NA	01/22/18	RL	Calculation
Total Phosphorous (P)	mg/L	0.012	0.005	01/19/18	MC	SM 4500-P-B,E
Ortho Phosphorous (P)	mg/L	BRL	0.005	01/19/18	MC	SM 4500-P

BRL=below reportable limits

**see attached*

By: _____
Ronald J. Saari
Laboratory Director